

新改第2号 島内松原線道路改良工事(2工区)

本 工 事 内 訳 書

(第一号様式13)

計 算 表

島内松原線(2工区)

総括数量

1	オープン掘削	196.0 m ³
2	機械床堀	29.0 m ³
3	基面整正	29.0 m ²
4	埋戻	11.6 m ³
	残土	212.1 m ³

測点	単距離	断 面				平均断面				立 積				適 要
		1	2	3	4	1	2	3	4	1	2	3	4	
No.27+14.0	0.00	3.4	0.5	0.5	0.2	1.70	0.25	0.25	0.10	0.0	0.0	0.0	0.0	
No.28	6.00	3.2	0.5	0.5	0.2	3.30	0.50	0.50	0.20	19.8	3.0	3.0	1.2	
No.28+8.0	8.00	3.3	0.5	0.5	0.2	3.25	0.50	0.50	0.20	26.0	4.0	4.0	1.6	
No.29	12.00	3.2	0.5	0.5	0.2	3.25	0.50	0.50	0.20	39.0	6.0	6.0	2.4	
No.30	20.00	3.6	0.5	0.5	0.2	3.40	0.50	0.50	0.20	68.0	10.0	10.0	4.0	
No.30+12.0	12.00	3.6	0.5	0.5	0.2	3.60	0.50	0.50	0.20	43.2	6.0	6.0	2.4	
小計	58.00									196.0	29.0	29.0	11.6	

(第一号様式13)

計 算 表

島内松原線(2工区)

13 表層工	391.5 m ²
14 上層路盤工	391.5 m ²
15 下層路盤工(10cm)	391.5 m ²
16 下層路盤工(20cm)	312.5 m ²

測点	単距離	断 面				平均断面				立 積				適 要
		13	14	15	16	13	14	15	16	13	14	15	16	
No.27+14.0	0.00	6.75	6.75	6.75	6.75	3.38	3.38	3.38	3.38	0.0	0.0	0.0	0.0	
No.28	6.00	6.75	6.75	6.75	5.75	6.75	6.75	6.75	6.25	40.5	40.5	40.5	37.5	
No.28+8.0	8.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.50	54.0	54.0	54.0	44.0	
No.29	12.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	81.0	81.0	81.0	63.0	
No.30	20.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	135.0	135.0	135.0	105.0	
No.30+12.0	12.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	81.0	81.0	81.0	63.0	
小計	58.00									391.5	391.5	391.5	312.5	

計 算 表

島内松原線(2工区)

総括数量

17 改良工 (t=50cm)	312.5 m ²
18 張コンクリート	40.6 m ²
19 不陸整正	391.5 m ²
20 舗装剥取	313.8 m ²

測点	単距離	断 面				平均断面				立 積				適 要
		17	18	19	20	17	18	19	20	17	18	19	20	
No.27+14.0	0.00	6.75	0.70	6.75	5.42	3.38	0.35	3.38	2.71	0.0	0.0	0.0	0.0	
No.28	6.00	5.75	0.70	6.75	5.42	6.25	0.70	6.75	5.42	37.5	4.2	40.5	32.5	
No.28+8.0	8.00	5.25	0.70	6.75	5.46	5.50	0.70	6.75	5.44	44.0	5.6	54.0	43.5	
No.29	12.00	5.25	0.70	6.75	5.4	5.25	0.70	6.75	5.42	63.0	8.4	81.0	65.0	
No.30	20.00	5.25	0.70	6.75	5.4	5.25	0.70	6.75	5.40	105.0	14.0	135.0	107.9	
No.30+12.0	12.00	5.25	0.70	6.75	5.4	5.25	0.70	6.75	5.41	63.0	8.4	81.0	64.9	
合計	58.00									312.5	40.6	391.5	313.8	

