

# 新改(社会)第1号 西岳2号線道路改良工事

## 本 工 事 内 訳 書





(第一号様式13)

# 計 算 表

西岳2号線(A工区)

総括数量

21	張 芝	0.0 m2
22	張コン(切土)	58.0 m2
23	張コン(盛土)	0.0 m2
24	車道舗装工	0.0 m2
21	張 芝	0.0 m2
22	張コン(切土)	58.0 m2
23	張コン(盛土)	0.0 m2
24	車道舗装工	0.0 m2

測点	単距離	断 面				平均断面				立 積				適 要
		21	22	23	24	21	22	23	24	21	22	23	24	
No.25+8.0	0.00		2.00				1.00				0.0			
+14.0	6.00		2.00				2.00				12.0			
No.26	6.00		2.00				2.00				12.0			
No.26+8.01	8.01		2.00				2.00				16.0			
No.26+14.0	5.99		2.00				2.00				12.0			
No.27+17.0	3.00		2.00				2.00				6.0			
小計	29.00									0.0	58.0	0.0	0.0	

(第一号様式13)

# 計 算 表

## 西岳2号線(A工区)

### 総括数量

17 路床盛土(4 < W)	0.0 m <sup>2</sup>
18 切土法面機械仕上(軟岩)	55.9 m <sup>2</sup>
19 植生基材吹付	10.5 m <sup>2</sup>
20 モルタル吹付	573.2 m <sup>2</sup>
17 路床盛土(4 < W)	0.0 m <sup>2</sup>
18 切土法面機械仕上(軟岩)	55.9 m <sup>2</sup>
19 植生基材吹付	10.5 m <sup>2</sup>
20 モルタル吹付	573.2 m <sup>2</sup>

測点	単距離	断 面				平均断面				立 積				適 要
		17	18	19	20	17	18	19	20	17	18	19	20	
No.25+8.0	0.00				0.0				0.00				0.0	
+14.0	6.00				4.0				2.00				12.0	
No.26	6.00				16.2				10.10				60.6	
No.26+8.01	8.01		4.3		28.2		2.15		22.20		17.2		177.8	
No.26+14.0	5.99		4.3		30		4.30		29.10		25.8		174.3	
No.26+17.0	3.00		4.3		30		4.30		30.00		12.9		90.0	
No.26+19.0	2.00				0				15.00				30.0	
No.27(26+19.0)	0.00				9.5				4.75				0.0	
No.27+2.0	3.00			7	9.5		3.50	9.50			10.5		28.5	
No.27+10.0														
小計	34.00									0.0	55.9	10.5	573.2	