

# 新改(電源)第 1 号 島内松原線道路改良工事

## 本 工 事 内 訳 書



(第一号様式13)

# 計 算 表

島内松原線

総括数量

1	オープン掘削	198.2 m3	掘削合計	271.8
2	機械床堀	73.6 m3	埋戻合計	33.6
3	埋戻	33.6 m2		
4		0.0 m3		
残土		234.5 m3		

測点	単距離	断 面				平均断面				立 積				適 要
		1	2	3	4	1	2	3	4	1	2	3	4	
No.24+10.0	0.00	2.5	3.3	1.4		1.25	1.65	0.70		0.0	0.0	0.0		
No.25	10.00	3.1	3.5	1.8		2.80	3.40	1.60		28.0	34.0	16.0		
No.25+8.80	8.80	2.8	0.5	0.2		2.95	2.00	1.00		26.0	17.6	8.8		
No.26	11.20	2.8	0.5	0.2		2.80	0.50	0.20		31.4	5.6	2.2		
No.27	20.00	3.6	0.5	0.2		3.20	0.50	0.20		64.0	10.0	4.0		
No.27+4.0	4.00	4.1	0.5	0.2		3.85	0.50	0.20		15.4	2.0	0.8		
No.27+12.8	8.80	3.5	0.5	0.2		3.80	0.50	0.20		33.4	4.4	1.8		
小計	62.80									198.2	73.6	33.6	0.0	

(第一号様式13)

# 計 算 表

島内松原線

総括数量

5	盛土 W=2.5	4.5 m <sup>3</sup>
6	盛土 W > 4.0	210.7 m <sup>3</sup>
7	盛土法面整形	136.3 m <sup>2</sup>
8	人工張芝	90.1 m <sup>3</sup>
必要購入土		215.2 m <sup>3</sup>

測点	単距離	断 面				平均断面				立 積				適要
		5	6	7	8	5	6	7	8	5	6	7	8	
No.21+16.0	0.00	0.1	6.8	3.3	2.3	0.05	3.40	1.65	1.15	0.0	0.0	0.0	0.0	
No.22	4.00	0.1	6.8	3.3	2.3	0.10	6.80	3.30	2.30	0.4	27.2	13.2	9.2	
No.22+10.0	10.00	0.0	5.5	3.3	2.3	0.05	6.15	3.30	2.30	0.5	61.5	33.0	23.0	
No.23	10.00	0.0	6.3	2.8	1.8	0.00	5.90	3.05	2.05	0.0	59.0	30.5	20.5	
No.24	20.00	0.0	0.0	2.6	1.6	0.00	3.15	2.70	1.70	0.0	63.0	54.0	34.0	
No.24+4.29	4.29	0.2	0.0	0.0	0.0	0.10	0.00	1.30	0.80	0.4	0.0	5.6	3.4	
No.25	15.71	0.0	0.0	0.0	0.0	0.10	0.00	0.00	0.00	1.6	0.0	0.0	0.0	
No.25+8.80	8.80	0.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00	0.0	0.0	0.0	0.0	
No.26	11.20	0.1	0.0	0.0	0.0	0.05	0.00	0.00	0.00	0.6	0.0	0.0	0.0	
No.27	20.00	0.0	0.0	0.0	0.0	0.05	0.00	0.00	0.00	1.0	0.0	0.0	0.0	
小計	104.00									4.5	210.7	136.3	90.1	

(第一号様式13)

# 計 算 表

島内松原線

総括数量

9	メンテナンスフリー(右側)	72.4 m3
10		0.0 m2
11		0.0 m2
12		0.0 m2

測点	単距離	断 面				平均断面				立 積				適 要
		9	10	11	12	9	10	11	12	9	10	11	12	
No.21+16.0	0.00	1.50				0.75				0.0				
No.22	4.00	1.50				1.50				6.0				
No.22+10.0	10.00	1.50				1.50				15.0				
No.23	10.00	1.50				1.50				15.0				
No.24	20.00	1.50				1.50				30.0				
No.24+4.29	4.29	1.50				1.50				6.4				
小計	44.29									72.4	0.0	0.0	0.0	

(第一号様式13)

# 計 算 表

島内松原線

総括数量

13	メンテナンスフリー(左側)	37.6 m <sup>2</sup>	(舗装面積図面)
14	基面整正	48.3 m <sup>2</sup>	
15		0.0 m <sup>2</sup>	
16		0.0 m <sup>2</sup>	

測点	単距離	断 面				平均断面				立 積				適 要
		13	14	15	16	13	14	15	16	13	14	15	16	
No.24+10.0	0.00	0.7	2.00			0.35	1.00			0.0	0.0			
No.25	10.00	1.4	1.50			1.05	1.75			10.5	17.5			
No.25+8.80	8.80	0.7	0.50			1.05	1.00			9.2	8.8			
No.26	11.20	0.7	0.50			0.70	0.50			7.8	5.6			
No.27	20.00	0.0	0.50			0.35	0.50			7.0	10.0			
No.27+4.0	4.00	0.0	0.50			0.00	0.50			0.0	2.0			
No.27+12.8	8.80	0.7	0.50			0.35	0.50			3.1	4.4			
小計	62.80									37.6	48.3	0.0	0.0	

# 計 算 表

## 島内松原線(2工区)

17	表層工	425.4 m <sup>2</sup>	(舗装面積図面)
18	上層路盤工	425.4 m <sup>2</sup>	(舗装面積図面)
19	下層路盤工(10cm)	425.4 m <sup>2</sup>	(舗装面積図面)
20	下層路盤工(20cm)	425.4 m <sup>2</sup>	(舗装面積図面)

測点	単距離	断 面				平均断面				立 積				適 要
		17	18	19	20	17	18	19	20	17	18	19	20	
No.24+10.0	0.00	7.01	7.01	7.01	7.01	3.51	3.51	3.51	3.51	0.0	0.0	0.0	0.0	
No.25	10.00	6.77	6.77	6.77	6.77	6.89	6.89	6.89	6.89	68.9	68.9	68.9	68.9	
No.25+8.80	8.80	6.75	6.75	6.75	6.75	6.76	6.76	6.76	6.76	59.5	59.5	59.5	59.5	
No.26	11.20	6.75	6.75	6.75	6.75	6.75	6.75	6.75	6.75	75.6	75.6	75.6	75.6	
No.27	20.00	6.75	6.75	6.75	6.75	6.75	6.75	6.75	6.75	135.0	135.0	135.0	135.0	
No.27+4.0	4.00	6.75	6.75	6.75	6.75	6.75	6.75	6.75	6.75	27.0	27.0	27.0	27.0	
No.27+12.8	8.80	6.75	6.75	6.75	6.75	6.75	6.75	6.75	6.75	59.4	59.4	59.4	59.4	
小計	62.80									425.4	425.4	425.4	425.4	

# 計 算 表

島内松原線(2工区)

総括数量

21	路肩舗装	22.4 m <sup>2</sup>	
22	改良工 (t=50cm)	425.4 m <sup>2</sup>	(舗装面積図面)
23	不陸整正	411.0 m <sup>2</sup>	
24	舗装剥取	0.0 m <sup>2</sup>	(舗装取壊図面)

測点	単距離	断 面				平均断面				立 積				適 要
		21	22	23	24	21	22	23	24	21	22	23	24	
No.24+10.0	0.00	0.00	7.01	6.01		0.00	3.51	3.01		0.0	0.0	0.0		
No.25	10.00	1.41	6.77	5.77		0.71	6.89	5.89		7.1	68.9	58.9		
No.25+8.80	8.80	0.60	6.75	6.75		1.01	6.76	6.26		8.8	59.5	55.1		
No.26	11.20	0.20	6.75	6.75		0.40	6.75	6.75		4.5	75.6	75.6		
No.27	20.00	0.00	6.75	6.75		0.10	6.75	6.75		2.0	135.0	135.0		
No.27+4.0	4.00	0.00	6.75	6.75		0.00	6.75	6.75		0.0	27.0	27.0		
No.27+12.8	8.80	0.00	6.75	6.75		0.00	6.75	6.75		0.0	59.4	59.4		
合計	62.80									22.4	425.4	411.0	0.0	