

西岳 2 号線道路改良工事 数量表

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

1	片切掘削普通土	0.0 m3
2	片切掘削軟岩	0.0 m3
3	オープン普通土	199.0 m3
4	オープン軟岩	0.0 m3
1	片切掘削普通土	0.0 m3
2	片切掘削軟岩	0.0 m3
3	オープン普通土	199.0 m3
4	オープン軟岩	0.0 m3

測点	単距離	断 面				平均断面				立 積				適要 (片切掘削 偏心補正距
		1	2	3	4	1	2	3	4	1	2	3	4	
+14.0	0.00			1.9				0.95				0.0		
No.24	6.00			3.5				2.70				16.2		
SP.7(No.24+15.11)	15.11			3.6				3.55				53.6		
No.25	4.89			3.0				3.30				16.1		
+4.6	4.60			2.2				2.60				12.0		
+14.0	9.40			3.0				2.60				24.4		
No.26	6.00			3.1				3.05				18.3		
EC.7(No.26+8.01)	8.01			3.4				3.25				26.0		
+14.0	5.99			3.7				3.55				21.3		
+17.0	3.00			3.7				3.70				11.1		
				0.0				1.85				0.0		
														7.2
														9.7
小計	63.00									0.0	0.0	199.0	0.0	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

5	床掘機械(W<2)普通土	44.7 m3
6	床掘機械(W<2)軟岩	0.0 m3
7	床掘機械(W>2)普通土	0.0 m3
8	埋戻 A(W2 ≥ 4)	0.0 m3
5	床掘機械(W<2)普通土	44.7 m3
6	床掘機械(W<2)軟岩	0.0 m3
7	床掘機械(W>2)普通土	0.0 m3
8	埋戻 A(W2 ≥ 4)	0.0 m3

測点	単距離	断 面				平均断面				立 積				適要
		5	6	7	8	5	6	7	8	5	6	7	8	
+14.0	0.00	0.8				0.40				0.0				
No.24	6.00	0.8				0.80				4.8				
SP.7(No.24+15.11)	15.11	0.6				0.70				10.6				
No.25	4.89	0.6				0.60				2.9				
+4.6	4.60	0.6				0.60				2.8				
+14.0	9.40	0.6				0.60				5.6				
No.26	6.00	0.6				0.60				3.6				
EC.7(No.26+8.01)	8.01	0.6				0.60				4.8				
EC.7(No.26+8.01)	0.00	1.0				0.80				0.0				
+14.0	5.99	1.1				1.05				6.3				
+17.0	3.00	1.1				1.10				3.3				
		0				0.55				0.0				
小計	63.00									44.7	0.0	0.0	0.0	

計 算 表

西岳2号線(A工区)

総括数量

9	埋戻B($W \leq W1 < 4, W2 < 1$)	0.0 m3
10	埋戻C($1 \leq W1 < 4, W2 < 1$)	0.0 m3
11	埋戻D ($W1 < 1, W2 < 1$)	16.2 m3
12	路体盛土 ($W < 2.5$)	0.0 m3
9	埋戻B($W \leq W1 < 4, W2 < 1$)	0.0 m3
10	埋戻C($1 \leq W1 < 4, W2 < 1$)	0.0 m3
11	埋戻D ($W1 < 1, W2 < 1$)	16.2 m3
12	路体盛土 ($W < 2.5$)	0.0 m3

測点	単距離	断 面				平均断面				立 積				適要
		9	10	11	12	9	10	11	12	9	10	11	12	
+14.0	0.00			0.4				0.20				0.0		
No.24	6.00			0.4				0.40				2.4		
SP.7(No.24+15.11)	15.11			0.2				0.30				4.5		
No.25	4.89			0.2				0.20				1.0		
+4.6	4.60			0.2				0.20				0.9		
+14.0	9.40			0.2				0.20				1.9		
No.26	6.00			0.2				0.20				1.2		
EC.7(No.26+8.01)	8.01			0.2				0.20				1.6		
EC.7(No.26+8.01)	0.00			0.3				0.25				0.0		
+14.0	5.99			0.3				0.30				1.8		
+17.0	3.00			0.3				0.30				0.9		
小計	63.00									0.0	0.0	16.2	0.0	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

13	路体盛土(2.5～4)	0.0 m3
14	路体盛土(4＜W)	0.0 m3
15	路床盛土(W＜2.5)	5.3 m2
16	路床盛土(2.5～4)	0.0 m2
13	路体盛土(2.5～4)	0.0 m3
14	路体盛土(4＜W)	0.0 m3
15	路床盛土(W＜2.5)	5.3 m2
16	路床盛土(2.5～4)	0.0 m2

測点	単距離	断 面				平均断面				立 積				適要
		13	14	15	16	13	14	15	16	13	14	15	16	
+14.0	0.00			0.2				0.10				0.0		
No.24	6.00			0.1				0.15				0.9		
SP.7(No.24+15.11)	15.11			0.1				0.10				1.5		
No.25	4.89			0.1				0.10				0.5		
+4.6	4.60			0.1				0.10				0.5		
+14.0	9.40			0.1				0.10				0.9		
No.26	6.00			0.1				0.10				0.6		
EC.7(No.26+8.01)	8.01			0.0				0.05				0.4		
+14.0	5.99													
+17.0	3.00													
小計	63.00									0.0	0.0	5.3	0.0	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

17	張 芝	0.0 m2
18	張コン(切土)	0.0 m2
19	張コン(盛土)	14.3 m2
20	車道舗装工	459.2 m2
17	張 芝	0.0 m2
18	張コン(切土)	0.0 m2
19	張コン(盛土)	14.3 m2
20	車道舗装工	459.2 m2

測点	単距離	断 面				平均断面				立 積				適要
		21	22	23	24	21	22	23	24	21	22	23	24	
+14.0	0.00				6.87				3.44				0.0	
No.24	6.00				6.87				6.87				41.2	
SP.7(No.24+15.11)	15.11				7.50				7.19				108.6	
No.25	4.89				7.50				7.50				36.7	
+4.6	4.60				7.50				7.50				34.5	
+14.0	9.40				7.50				7.50				70.5	
No.26	6.00				7.41				7.46				44.7	
EC.7(No.26+8.01)	8.01				7.25				7.33				58.7	
EC.7(No.26+8.01)	0.00			1.50	7.25			0.75	7.25			0.0	0.0	
+14.0	5.99			1.50	7.13			1.50	7.19			9.0	43.1	
+17.0	3.00			2.00	7.01			1.75	7.07			5.3	21.2	
小計	63.00									0.0	0.0	14.3	459.2	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

21	歩道舗装工	0.0 m ²
22	路盤工	459.2 m ²
23	不陸整正	425.7 m ³
24	基面整正	43.2 m ²

21	歩道舗装工	0.0 m ²
22	路盤工	459.2 m ²
23	不陸整正	425.7 m ³
24	基面整正	43.2 m ²

測点	単距離	断 面				平均断面				立 積				適要
		25	26	27	28	25	26	27	28	25	26	27	28	
+14.0	0.00		6.87	6.32	0.60		3.44	3.16	0.30		0.0	0.0	0.0	
No.24	6.00		6.87	6.32	0.60		6.87	6.32	0.60		41.2	37.9	3.6	
SP.7(No.24+15.11)	15.11		7.50	6.96	0.60		7.19	6.64	0.60		108.6	100.3	9.1	
No.25	4.89		7.50	6.96	0.60		7.50	6.96	0.60		36.7	34.0	2.9	
+4.6	4.60		7.50	6.96	0.60		7.50	6.96	0.60		34.5	32.0	2.8	
+14.0	9.40		7.50	6.96	0.60		7.50	6.96	0.60		70.5	65.4	5.6	
No.26	6.00		7.41	6.87	0.60		7.46	6.92	0.60		44.7	41.5	3.6	
EC.7(No.26+8.01)	8.01		7.25	6.71	0.60		7.33	6.79	0.60		58.7	54.4	4.8	
EC.7(No.26+8.01)	0.00		7.25	6.71	1.20		7.25	6.71	0.90		0.0	0.0	0.0	
+14.0	5.99		7.13	6.59	1.20		7.19	6.65	1.20		43.1	39.8	7.2	
+17.0	3.00		7.01	7.01	1.20		7.07	6.80	1.20		21.2	20.4	3.6	
小計	63.00									0.0	459.2	425.7	43.2	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

25	車道舗装撤去	344.3	m2
			m2
			m3
			m2
25	車道舗装撤去	344.3	m2
			m2
			m3
			m2

測点	単距離	断 面				平均断面				立 積				適要
		29	30	31	32	29	30	31	32	29	30	31	32	
+14.0	0.00	4.75				2.38				0.0				
No.24	6.00	4.72				4.74				28.4				
SP.7(No.24+1	15.11	5.43				5.08				76.7				
No.25	4.89	6.34				5.89				28.8				
+4.6	4.60	6.74				6.54				30.1				
+14.0	9.40	6.11				6.43				60.4				
No.26	6.00	5.47				5.79				34.7				
EC.7(No.26+3	8.01	5.08				5.28				42.3				
+14.0	5.99	4.73				4.91				29.4				
+17.0	3.00	4.26				4.50				13.5				
小計	63.00									344.3	0.0	0.0	0.0	