

市道 大里工業団地下線

		掘 削			床 掘			埋 戻			盛 土			基面整正		
測点	単距離	断面積	平均断面積	立 積	断面積	平均断面積	立 積	断面積	平均断面積	立 積	断面積	平均断面積	立 積	幅	平均幅	面 積
BP		1.1	0.55		1.1	0.55		0.6	0.30					1.2	0.60	
+2.0	2.00	1.0	1.05	2.10	1.1	1.10	2.20	0.6	0.60	1.20	0.5	0.25	0.50	1.2	1.20	2.40
+9.0	7.00	0.9	0.95	6.65	1.3	1.20	8.40	0.6	0.60	4.20	0.7	0.60	4.20	1.2	1.20	8.40
+16.0	7.00	0.7	0.80	5.60	1.2	1.25	8.75	0.5	0.55	3.85	0.5	0.60	4.20	1.1	1.15	8.05
+23.0	7.00	0.7	0.70	4.90	1.2	1.20	8.40	0.5	0.50	3.50	0.5	0.50	3.50	1.1	1.10	7.70
+28.8	5.80	1.0	0.85	4.93	1.3	1.25	7.25	0.5	0.50	2.90		0.25	1.45	1.0	1.05	6.09
+28.8			0.50		0.4	0.85		0.1	0.30					0.3	0.65	
+31.5	2.70				0.4	0.40	1.08	0.1	0.10	0.27				0.3	0.30	0.81
合計	31.50			24.18			36.08			15.92			13.85			33.45
残土処理 $24.18 + 36.08 - 15.92/0.9 - 13.85/0.9 =$ 27.18 27.18 m3																