

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

1	片切掘削普通土	123.6 m3
2	片切掘削軟岩	400.4 m3
3	オープン普通土	91.6 m3
4	オープン軟岩	1051.8 m3
1	片切掘削普通土	123.6 m3
2	片切掘削軟岩	400.4 m3
3	オープン普通土	91.6 m3
4	オープン軟岩	1051.8 m3

測点	単距離	断 面				平均断面				立 積				適要 (片切掘削 偏心補正距
		1	2	3	4	1	2	3	4	1	2	3	4	
B.P(No.26+17.0)	0.00													
No.27	3.00				40.0				20.00				60.0	
+10.0	10.00	16.8	65.0			8.40	32.50			84.0	325.0			
No.28	10.00			6.8	56.7			3.40	28.35			34.0	283.5	
+9.0	9.00			0.7	31.8			3.75	44.25			33.8	398.3	
No.29	11.00	7.2	13.7	3.63	24.6	3.60	6.85	2.17	28.18	39.6	75.4	23.8	310.0	
小計	43.00									123.6	400.4	91.6	1051.8	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

17	路床盛土(4 < W)	0.0 m2
18	切土法面機械仕上	0.0 m2
19	盛土法面機械仕上	0.0 m2
20	植生基材吹付	740.8 m2
17	路床盛土(4 < W)	0.0 m2
18	切土法面機械仕上	0.0 m2
19	盛土法面機械仕上	0.0 m2
20	植生基材吹付	740.8 m2

測点	単距離	断 面				平均断面				立 積				適要
		17	18	19	20	17	18	19	20	17	18	19	20	
B.P(No.26+17.0)	0.00													
No.27	3.00				28.9				14.45				43.4	
+10.0	10.00				23.7				26.30				263.0	
No.28	10.00				18.4				21.05				210.5	
+9.0	9.00				16.6				17.50				157.5	
+13.0	4.00				16.6				16.60				66.4	
小計	36.00									0.0	0.0	0.0	740.8	