

工事数量総括表

工 種	種 別	名 称	規格	単位	数 量	摘 要
土工						
		掘削		m3	86.7	
		土砂等運搬	運搬距離L=0.3km以下	m3	86.7	
		整地		m3	86.7	
法面工						
		張コンクリート	t=7cm	m2	307.7	本線部
		張コンクリート	t=7cm	m2	70.0	河川上流部
舗装工						
	車道舗装	表層	密粒度As t=5cm	m2	833.1	平江1号部
		上層路盤	粒調碎石 t=15cm	m2	833.1	〃
		下層路盤	再生碎石 t=10cm	m2	645.9	〃
		下層路盤	再生碎石 t=15cm	m2	155.0	
		下層路盤	購入シラス t=20cm	m2	155.0	〃
		表層	密粒度As t=5cm	m2	171.3	都心平江部 No. 9～No. 10+10 W5.71m*L30.0m =171.3m2
		上層路盤	粒調碎石 t=8cm	m2	171.3	
排水工						
		2号横断暗渠工		式	1.0	
縁石工						
		3型	歩道乗入部	m	18.4	
付帯工						
	区画線工	実線白色	15cm幅	m	698.7	
		破線白色	15cm幅	m	199.0	
		実線白色	45cm幅	m	252.3	
		文字白色	15cm幅換算	m	294.0	

工事数量総括表

[illegible]

都心平江線道路築造工事(3工区)土量計算書

1/2

測点	単距離	法面工(張コンクリート)			舗装工(表層、上層路盤)			下層路盤工(RC-40)t=100			下層路盤工(RC-40)t=150			下層路盤工(購入シラス)		
		断 面	平均断面	面 積	断 面	平均断面	面 積	断 面	平均断面	面 積	断 面	平均断面	面 積	断 面	平均断面	面 積
No.0	0.000	3.90			5.01			4.61								
BP+10.0	10.000	3.70	3.80	38.0	6.50	5.76	57.6	6.10	5.36	53.6		0.00	0.0		0.00	0.0
No.1	10.000	3.40	3.55	35.5	6.50	6.50	65.0	6.10	6.10	61.0		0.00	0.0		0.00	0.0
No.1+10.0	10.000	4.00	3.70	37.0	6.50	6.50	65.0	6.10	6.10	61.0		0.00	0.0		0.00	0.0
No.2	10.000	4.80	4.40	44.0	6.50	6.50	65.0	6.10	6.10	61.0		0.00	0.0		0.00	0.0
SP.1	4.549	5.10	4.95	22.5	6.50	6.50	29.6	6.10	6.10	27.7		0.00	0.0		0.00	0.0
No.2+10.0	5.451	5.60	5.35	29.2	6.88	6.69	36.5	6.88	6.49	35.4		0.00	0.0		0.00	0.0
No.2+17.75	7.750		2.80	21.7	21.35	14.12	109.4	21.35	14.12	109.4		0.00	0.0		0.00	0.0
No.3	2.250		0.00	0.0	21.35	21.35	48.0	21.35	21.35	48.0		0.00	0.0		0.00	0.0
BC.2	8.757	5.40	2.70	23.6	6.50	13.93	122.0	6.10	13.73	120.2		0.00	0.0		0.00	0.0
SP.2	3.622	5.60	5.50	19.9	6.50	6.50	23.5	6.10	6.10	22.1		0.00	0.0		0.00	0.0
EC.2	3.622	4.40	5.00	18.1	6.50	6.50	23.5	6.10	6.10	22.1		0.00	0.0		0.00	0.0
No.4	3.999	4.70	4.55	18.2	6.50	6.50	26.0	6.10	6.10	24.4		0.00	0.0		0.00	0.0
No.4	0.000		2.35	0.0	6.50	6.50	0.0		3.05	0.0	6.10	3.05	0.0	6.10	3.05	0.0
No.4+10.0	10.000		0.00	0.0	6.00	6.25	62.5		0.00	0.0	5.80	5.95	59.5	5.80	5.95	59.5
IP.3	3.012		0.00	0.0	6.00	6.00	18.1		0.00	0.0	5.80	5.80	17.5	5.80	5.80	17.5
No.5	6.988		0.00	0.0	4.97	5.49	38.4		0.00	0.0	4.77	5.29	37.0	4.77	5.29	37.0
No.5+10.0	10.000		0.00	0.0	3.63	4.30	43.0		0.00	0.0	3.43	4.10	41.0	3.43	4.10	41.0
計	110.000			307.7			833.1			645.9			155.0			155.0

測点	単距離	掘削														
		断 面	平均断面	面 積	断 面	平均断面	面 積	断 面	平均断面	面 積	断 面	平均断面	面 積	断 面	平均断面	面 積
No.0	0.000															
BP+10.0	10.000		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.1	10.000		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.1+10.0	10.000		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.2	10.000		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
SP.1	4.549		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.2+10.0	5.451		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.2+17.75	7.750		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.3	2.250		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
BC.2	8.757		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
SP.2	3.622		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
EC.2	3.622		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.4	3.999		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.4	0.000	3.50	1.75	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.4+10.0	10.000	3.20	3.35	33.5		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
IP.3	3.012	3.20	3.20	9.6		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.5	6.988	2.70	2.95	20.6		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
No.5+10.0	10.000	1.90	2.30	23.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
計	110.000			86.7			0.0			0.0			0.0			0.0