

市道 岩下線

測点	単距離	掘削			床掘			埋戻			盛土			基面修正		
		断面積	平均断面積	立積	断面積	平均断面積	立積	断面積	平均断面積	立積	断面積	平均断面積	立積	幅	平均幅	面積
-3.5																
BP	3.50	4.3	2.15	7.53	1.8	0.90	3.15	1.1	0.55	1.93				1.1	0.55	1.93
+3.0	3.00	3.3	3.80	11.40	2.0	1.90	5.70	1.1	1.10	3.30	0.2	0.10	0.30	1.1	1.10	3.30
+6.0	3.00	4.8	4.05	12.15	1.6	1.80	5.40	1.1	1.10	3.30	0.1	0.15	0.45	1.1	1.10	3.30
-9.5	3.50		2.40	8.40		0.80	2.80		0.55	1.93		0.05	0.18		0.55	1.93
合計	13.00			39.48			17.05			10.45			0.93			10.45
残土処理							$39.475 + 17.05 - 10.45/0.9 - 0.925/0.9 =$					43.89 m3				