

新改(電源)第2号 島内松原線道路改良工事

本 工 事 内 訳 書

計 算 表

島内松原線

総括数量

1	オープン掘削	394.3 m3	
2	機械床堀	45.2 m3	
3	基面整正	67.8 m2	側溝分
4	埋戻	11.3 m3	
	残土	426.9 m3	

測点	単距離	断 面				平均断面				立 積				適要
		1	2	3	4	1	2	3	4	1	2	3	4	
NO.30+12.0	0.00	3.6	0.4	0.6	0.1	1.80	0.20	0.30	0.05	0.0	0.0	0.0	0.0	
NO.31	8.00	3.9	0.4	0.6	0.1	3.75	0.40	0.60	0.10	30.0	3.2	4.8	0.8	
NO.32	20.00	3.7	0.4	0.6	0.1	3.80	0.40	0.60	0.10	76.0	8.0	12.0	2.0	
NO.32+7.0	7.00	3.5	0.4	0.6	0.1	3.60	0.40	0.60	0.10	25.2	2.8	4.2	0.7	
KE6-1	6.34	3.4	0.4	0.6	0.1	3.45	0.40	0.60	0.10	21.9	2.5	3.8	0.6	
NO.33	6.66	3.5	0.4	0.6	0.1	3.45	0.40	0.60	0.10	23.0	2.7	4.0	0.7	
NO.33+14.0	14.00	3.3	0.4	0.6	0.1	3.40	0.40	0.60	0.10	47.6	5.6	8.4	1.4	
NO.34	6.00	3.5	0.4	0.6	0.1	3.40	0.40	0.60	0.10	20.4	2.4	3.6	0.6	
NO.34+6.0	6.00	3.3	0.4	0.6	0.1	3.40	0.40	0.60	0.10	20.4	2.4	3.6	0.6	
KA6-2	6.97	3.2	0.4	0.6	0.1	3.25	0.40	0.60	0.10	22.7	2.8	4.2	0.7	
NO.35	7.03	3.1	0.4	0.6	0.1	3.15	0.40	0.60	0.10	22.1	2.8	4.2	0.7	
NO.36	20.00	3.6	0.4	0.6	0.1	3.35	0.40	0.60	0.10	67.0	8.0	12.0	2.0	
NO.36+5.0	5.00	3.6	0.4	0.6	0.1	3.60	0.40	0.60	0.10	18.0	2.0	3.0	0.5	
小計	113.00									394.3	45.2	67.8	11.3	

(第一号様式13)

計 算 表

島内松原線

13 表 層 工	762.9 m ²
14 上 層 路 盤 工	762.9 m ²
15 下 層 路 盤 工(10cm)	762.9 m ²
16 下 層 路 盤 工(20cm)	593.4 m ²

測点	単距離	断 面				平均断面				立 積				適要
		13	14	15	16	13	14	15	16	13	14	15	16	
NO.30+12.0	0.00	6.75	6.75	6.75	5.25	3.38	3.38	3.38	2.63	0.0	0.0	0.0	0.0	
NO.31	8.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	54.0	54.0	54.0	42.0	
NO.32	20.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	135.0	135.0	135.0	105.0	
NO.32+7.0	7.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	47.3	47.3	47.3	36.8	
KE6-1	6.34	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	42.8	42.8	42.8	33.3	
NO.33	6.66	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	45.0	45.0	45.0	35.0	
NO.33+14.0	14.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	94.5	94.5	94.5	73.5	
NO.34	6.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	40.5	40.5	40.5	31.5	
NO.34+6.0	6.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	40.5	40.5	40.5	31.5	
KA6-2	6.97	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	47.0	47.0	47.0	36.6	
NO.35	7.03	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	47.5	47.5	47.5	36.9	
NO.36	20.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	135.0	135.0	135.0	105.0	
NO.36+5.0	5.00	6.75	6.75	6.75	5.25	6.75	6.75	6.75	5.25	33.8	33.8	33.8	26.3	
小計	113.00									762.9	762.9	762.9	593.4	

(第一号様式13)

計 算 表

島内松原線

総括数量

17 改良工 (t=50cm)	593.4 m ²
18 張コンクリート	56.5 m ²
19 不陸整正	762.9 m ²
20 舗装剥取	608.9 m ²

測点	単距離	断 面				平均断面				立 積				適 要
		17	18	19	20	17	18	19	20	17	18	19	20	
NO.30+12.0	0.00	5.25	0.50	6.75	5.41	2.63	0.25	3.38	2.71	0.0	0.0	0.0	0.0	
NO.31	8.00	5.25	0.50	6.75	5.57	5.25	0.50	6.75	5.49	42.0	4.0	54.0	43.9	
NO.32	20.00	5.25	0.50	6.75	5.63	5.25	0.50	6.75	5.60	105.0	10.0	135.0	112.0	
NO.32+7.0	7.00	5.25	0.50	6.75	5.62	5.25	0.50	6.75	5.63	36.8	3.5	47.3	39.4	
KE6-1	6.34	5.25	0.50	6.75	5.62	5.25	0.50	6.75	5.62	33.3	3.2	42.8	35.6	
NO.33	6.66	5.25	0.50	6.75	5.23	5.25	0.50	6.75	5.43	35.0	3.3	45.0	36.1	
NO.33+14.0	14.00	5.25	0.50	6.75	5.05	5.25	0.50	6.75	5.14	73.5	7.0	94.5	72.0	
NO.34	6.00	5.25	0.50	6.75	5.11	5.25	0.50	6.75	5.08	31.5	3.0	40.5	30.5	
NO.34+6.0	6.00	5.25	0.50	6.75	5.22	5.25	0.50	6.75	5.17	31.5	3.0	40.5	31.0	
KA6-2	6.97	5.25	0.50	6.75	5.32	5.25	0.50	6.75	5.27	36.6	3.5	47.0	36.7	
NO.35	7.03	5.25	0.50	6.75	5.37	5.25	0.50	6.75	5.35	36.9	3.5	47.5	37.6	
NO.36	20.00	5.25	0.50	6.75	5.36	5.25	0.50	6.75	5.37	105.0	10.0	135.0	107.3	
NO.36+5.0	5.00	5.25	0.50	6.75	5.36	5.25	0.50	6.75	5.36	26.3	2.5	33.8	26.8	
合計	113.00									593.4	56.5	762.9	608.9	