

普通河川 吉村川

測点	単距離	掘削			床掘			埋戻			法面整形			張コンクリート		
		断面積	平均断面積	立積	断面積	平均断面積	立積	断面積	平均断面積	立積	断面積	平均断面積	立積	断面積	平均断面積	立積
BP	-				1.6			1.3			0.7			0.6		
+8.5	8.50	0.3	0.15	1.28	0.6	1.10	9.35	1.2	1.25	10.63	0.2	0.45	3.83	1.3	0.95	8.08
+17.5	9.00	0.7	0.50	4.50	1.0	0.80	7.20	1.2	1.20	10.80	0.4	0.30	2.70	1.5	1.40	12.60
+24.0	6.50	0.4	0.55	3.58	1.0	1.00	6.50	1.3	1.25	8.13	1.0	0.70	4.55	1.6	1.55	10.08
+34.5	10.50	0.7	0.55	5.78	2.9	1.95	20.48	3.2	2.25	23.63	3.1	2.05	21.53	3.9	2.75	28.88
+52.0	17.50	0.4	0.55	9.63	2.6	2.75	48.13	3.1	3.15	55.13	2.8	2.95	51.63	3.8	3.85	67.38
+58.0	6.00	2.1	1.25	7.50	4.2	3.40	20.40	4.3	3.70	22.20	3.1	2.95	17.70	4.3	4.05	24.30
合計	58.00			32.25			112.05			130.50			101.93			151.30

発生土処分費 (32.25+112.05)/2=72.15

72.15 m3

購入土 (32.25+112.05)/2-130.5/0.9=-72.85

72.85 m3

