

計 算 表

西岳2号線(A工区)

総括数量

1	片切掘削普通土	132.5 m3
2	片切掘削軟岩	203.9 m3
3	オープン普通土	505.0 m3
4	オープン軟岩	605.8 m3
残 土		1447.2 m3

測点	単距離	断 面				平均断面				立 積				適要 (片切掘削 偏心補正距
		1	2	3	4	1	2	3	4	1	2	3	4	
EC.7(No.26+8.01)	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00	0.0	0.0	0.0	0.0	
+14.0(+16.0)	7.99	11.4	21.0	40.3	49.4	5.70	10.50	20.15	24.70	45.5	83.9	161.0	197.4	
No.27	4.00	10.7	13.0	43.9	51.6	11.05	17.00	42.10	50.50	44.2	68.0	168.4	202.0	
No.27+8.0 地山摺付区間	8.00	0.0	0.0	0.0	0.0	5.35	6.50	21.95	25.80	42.8	52.0	175.6	206.4	
														7.2
														9.7
小計	19.99									132.5	203.9	505.0	605.8	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

17 路床盛土(4 < W)	0.0 m ²
18 切土法面機械仕上(普通土)	0.0 m ²
19 切土法面機械仕上(軟岩)	377.2 m ²
20 植生基材吹付	0.0 m ²
17 路床盛土(4 < W)	0.0 m ²
18 切土法面機械仕上(普通土)	0.0 m ²
19 切土法面機械仕上(軟岩)	377.2 m ²
20 植生基材吹付	0.0 m ²

測点	単距離	断 面				平均断面				立 積				適要
		17	18	19	20	17	18	19	20	17	18	19	20	
EC.7(No.26+8.01)	0.00		0.0	0.0		0.00	0.00			0.0	0.0			
+14.0(+16.0)	7.99		0.0	33.2		0.00	16.60			0.0	132.6			
No.27	4.00		0.0	29.7		0.00	31.45			0.0	125.8			
No.27+8.0	8.00		0.0	0.0		0.00	14.85			0.0	118.8			
														7.2
														9.7
小計	19.99									0.0	0.0	377.2	0.0	

(第一号様式13)

計 算 表

西岳2号線(A工区)

総括数量

21	張 芝	0.0 m ²
22	張コン(切土)	52.5 m ²
23	張コン(盛土)	0.0 m ²
24	車道舗装工	0.0 m ²
21	張 芝	0.0 m ²
22	張コン(切土)	52.5 m ²
23	張コン(盛土)	0.0 m ²
24	車道舗装工	0.0 m ²

測点	単距離	断 面				平均断面				立 積				適要
		21	22	23	24	21	22	23	24	21	22	23	24	
No.25+16.5	0.00		1.40				0.70							
No.26	3.50		1.40				1.40				4.9			
EC.7(No.26+8.01)	8.01		2.8				2.10				16.8			
+14.0(+16.0)	7.99		2.8				2.80				22.4			
No.27	4.00		1.4				2.10				8.4			
小計	23.50									0.0	52.5	0.0	0.0	