

市道 麓袴田線

測点	単距離	掘削			床掘			埋戻			盛土			不陸整正		
		断面積	平均断面積	立積	断面積	平均断面積	立積	断面積	平均断面積	立積	断面積	平均断面積	立積	幅	平均幅	面積
-0.90														3.6	1.80	
BP	0.90				1.4	0.70	0.63	0.4	0.20	0.18				2.8	3.20	2.88
+0.40	0.40				1.6	1.50	0.60	0.6	0.50	0.20				3.1	2.95	1.18
+1.10	0.70				1.3	1.45	1.02	0.6	0.60	0.42				3.5	3.30	2.31
+5.00	3.90				1.1	1.20	4.68	0.5	0.55	2.15				3.4	3.45	13.46
+10.00	5.00				0.9	1.00	5.00	0.4	0.45	2.25				3.5	3.45	17.25
No.1	10.00				1.1	1.00	10.00	0.5	0.45	4.50				3.6	3.55	35.50
+10.00	10.00				1.0	1.05	10.50	0.4	0.45	4.50				3.7	3.65	36.50
+15.00	5.00				1.3	1.15	5.75	0.5	0.45	2.25				3.7	3.70	18.50
No.2	5.00				1.0	1.15	5.75	0.4	0.45	2.25				3.7	3.70	18.50
+3.80	3.80				1.1	1.05	3.99	0.5	0.45	1.71				5.5	4.60	17.48
+4.00	0.20				1.6	1.35	0.27	0.5	0.50	0.10				3.4	4.45	0.89
+4.60	0.60				0.9	1.25	0.75	0.5	0.50	0.30				5.5	4.45	2.67
+6.00	1.40				0.4	0.65	0.91	0.3	0.40	0.56				5.6	5.55	7.77
+8.00	2.00				0.4	0.40	0.80	0.3	0.30	0.60				5.4	5.50	11.00
IP.1	1.65				0.4	0.40	0.66	0.2	0.25	0.41				3.7	4.55	7.51
IP.1						0.20			0.10					4.0	3.85	
+13.00	3.35													4.0	4.00	13.40
No.3	7.00													3.9	3.95	27.65
+5.00	5.00													3.9	3.90	19.50
小計	65.90						51.31			22.38						253.95

