

八房川線道路改良工事 数量計算書

工 種	種 別	細 別	規 格	単 位	数量	備考
土工		切土		m ³	0.0	
		盛土	81.4/0.9	m ³	90.4	
		購入土		m ³	90.4	
		残土処理		m ³	0.0	
法面整形工		切土法面整形		m ²	0.0	
		盛土法面整形		m ²	109.2	73.2+36.0
法面保護工	切土法面保護	張芝		m ²	0.0	
	盛土法面保護	張芝		m ²	109.2	73.2+36.0
舗装工	車道舗装工	表層工	再生密粒度 As(13) t=4cm	m ²	790.3	
		上層路盤	粒調碎石(30) t=7cm	m ²	136.7	
		下層路盤	再生碎石(40) t=10cm	m ²	115.9	
		不陸整正		m ²	655.0	
撤去・取壊工	AS舗装	切断		m	4.8	
		破碎		m ²	508.2	
		As殻処理	t=4cm	m ³	20.3	

土量計算書

測点	単距離	切土			盛土			車道舗装 (表層)			上層路盤			下層路盤		
		断面	平均断面	立 積	断面	平均断面	立 積	断面	平均断面	立 積	断面	平均断面	立 積	断面	平均断面	立 積
BP-6.31	0.000	0.00			0.00			4.00			0.00			0.00		
BP-2.87	3.440	0.00	0.00	0.0	0.00	0.00	0.0	4.00	4.00	13.8	0.00	0.00	0.0	0.00	0.00	0.0
BP	2.870	0.00	0.00	0.0	0.00	0.00	0.0	6.00	5.00	14.4	0.00	0.00	0.0	0.00	0.00	0.0
No.1	20.000	0.00	0.00	0.0	0.00	0.00	0.0	6.00	6.00	120.0	0.00	0.00	0.0	0.00	0.00	0.0
No.1	0.000	0.00	0.00	0.0	1.25	0.63	0.0	6.00	6.00	0.0	1.62	0.81	0.0	1.42	0.71	0.0
No.2	20.000	0.00	0.00	0.0	1.16	1.21	24.2	6.00	6.00	120.0	1.97	1.80	36.0	1.77	1.60	32.0
No.3	20.000	0.00	0.00	0.0	0.90	1.03	20.6	6.00	6.00	120.0	1.39	1.68	33.6	1.19	1.48	29.6
No.4	20.000	0.00	0.00	0.0	0.96	0.93	18.6	6.00	6.00	120.0	0.90	1.15	23.0	0.70	0.95	19.0
No.5	20.000	0.00	0.00	0.0	0.38	0.67	13.4	6.00	6.00	120.0	1.09	1.00	20.0	0.89	0.80	16.0
No.6	20.000	0.00	0.00	0.0	0.06	0.22	4.4	6.00	6.00	120.0	0.94	1.02	20.4	0.74	0.82	16.4
EP(No.6+7.78)	7.780	0.00	0.00	0.0	0.00	0.03	0.2	4.81	5.41	42.1	0.00	0.47	3.7	0.00	0.37	2.9
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0
計	134.090			0.0			81.4			790.3			136.7			115.9

測点	単距離	不陸整正			法面整正(切土)			法面整形(盛土)			撤去・取壊工					
		断面	平均断面	立 積	断面	平均断面	立 積	断面	平均断面	立 積	断面	平均断面	立 積	断面	平均断面	立 積
BP-6.31	0.000	4.00			0.00			0.00			0.00					
BP-2.87	3.440	4.00	4.00	13.8	0.00	0.00	0.0	0.00	0.00	0.0	0.00	0.00	0.0			
BP	2.870	6.00	5.00	14.4	0.00	0.00	0.0	0.00	0.00	0.0	0.00	0.00	0.0			
No.1	20.000	6.00	6.00	120.0	0.00	0.00	0.0	0.00	0.00	0.0	0.00	0.00	0.0			
No.1	0.000	4.38	5.19	0.0	0.00	0.00	0.0	1.28	0.64	0.0	4.40	2.20	0.0			
No.2	20.000	4.04	4.21	84.2	0.00	0.00	0.0	1.24	1.26	25.2	4.05	4.23	84.6			
No.3	20.000	4.61	4.33	86.6	0.00	0.00	0.0	0.87	1.06	21.2	4.61	4.33	86.6			
No.4	20.000	5.11	4.86	97.2	0.00	0.00	0.0	0.60	0.74	14.8	5.10	4.86	97.2			
No.5	20.000	4.92	5.02	100.4	0.00	0.00	0.0	0.30	0.45	9.0	4.92	5.01	100.2			
No.6	20.000	5.07	5.00	100.0	0.00	0.00	0.0	0.00	0.15	3.0	5.06	4.99	99.8			
EP(No.6+7.78)	7.780	4.81	4.94	38.4	0.00	0.00	0.0	0.00	0.00	0.0	5.15	5.11	39.8			
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0			
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0			
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0			
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0			
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0			
			0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0			
計	134.090			655.0			0.0			73.2			508.2			

BP+5.8～NO.1までA=36.0m2

計 109.2