

計 算 表

西浜町5号線

①	機 械 掘 削	0.0 m ³
②	機 械 床 掘	95.0 m ³
③	埋 戻	49.3 m ³
④	盛 土	0.0 m ³

残 土 処 理	40.2 m ³
(機械掘削 + 機械床掘 - 埋戻/0.9 - 盛土/0.9)	

測点	単距離	断 面				平均断面				立 積				適 要
		①	②	③	④	①	②	③	④	①	②	③	④	
B.P	0.00		0.9	0.4										
No.1	20.00		1.0	0.4		0.95	0.40			19.0	8.0			
No.2	20.00		0.9	0.4		0.95	0.40			19.0	8.0			
No.3	20.00		0.9	0.4		0.90	0.40			18.0	8.0			
+8.9	8.90		0.9	0.4		0.90	0.40			8.0	3.6			
IP.1	2.70		1.6	0.8		1.25	0.60			3.4	1.6			
IP.2	0.00		1.6	0.8		1.60	0.80			0.0	0.0			
+18.3	2.70		0.8	0.6		1.20	0.70			3.2	1.9			
No.4	1.70		0.8	0.6		0.80	0.60			1.4	1.0			
No.5	20.00		0.8	0.6		0.80	0.60			16.0	12.0			
+8.7	8.70		0.8	0.6		0.80	0.60			7.0	5.2			
	104.70									0.0	95.0	49.3	0.0	

計 算 表

1/2

西浜町5号線

⑤ 不陸整正	228.6 m ²
⑥	0.0 m ³
⑦	0.0 m ³
⑧	0.0 m ³

測点	単距離	断 面				平均断面				立 積				適 要
		⑤	⑥	⑦	⑧	⑤	⑥	⑦	⑧	⑤	⑥	⑦	⑧	
B.P	0.00	2.0												
No.1	20.00	2.0				2.00				40.0				
No.2	20.00	2.0				2.00				40.0				
No.3	20.00	2.0				2.00				40.0				
+8.9	8.90	2.0				2.00				17.8				
IP.1	2.70	8.9				5.45				14.7				
IP.2	0.00	8.4				8.65				0.0				
+18.3	2.70	2.0				5.20				14.0				
No.4	1.70	2.0				2.00				3.4				
No.5	20.00	2.0				2.00				40.0				
+8.7	8.70	2.3				2.15				18.7				
合計	104.70									228.6	0.0	0.0	0.0	