

計 算 表

塩屋・御倉町線

①	機 械 掘 削	0.0 m ³
②	機 械 床 掘	33.3 m ³
③	埋 戻	17.2 m ³
④	盛 土	0.0 m ³

残 土 処 理	14.2 m ³
(機械掘削 + 機械床掘 - 埋戻/0.9 - 盛土/0.9)	

測点	単距離	断 面				平均断面				立 積				適 要
		①	②	③	④	①	②	③	④	①	②	③	④	
B.P	0.00		0.7	0.6										
+4.2	4.20		0.8	0.4		0.75	0.50			3.2	2.1			
No.1	15.80		0.8	0.4		0.80	0.40			12.6	6.3			
No.2	20.00		0.8	0.4		0.80	0.40			16.0	8.0			
+1.9	1.90		0.8	0.4		0.80	0.40			1.5	0.8			
	41.90									0.0	33.3	17.2	0.0	

計 算 表

塩屋・御倉町線

⑤ 不陸修正	173.7 m ²
⑥	0.0 m ³
⑦	0.0 m ³
⑧	0.0 m ³

測点	単距離	断 面				平均断面				立 積				適 要
		⑤	⑥	⑦	⑧	⑤	⑥	⑦	⑧	⑤	⑥	⑦	⑧	
B.P	0.00	6.9												
+4.2	4.20	4.0			5.45				22.9					
No.1	15.80	4.0			4.00				63.2					
No.2	20.00	4.0			4.00				80.0					
+1.9	1.90	4.0			4.00				7.6					
合計	41.90								173.7	0.0	0.0	0.0		