



















# 計 算 表

1/2

## 浜田町4号線

①	機 械 掘 削	0.0 m <sup>3</sup>
②	機 械 床 掘	39.4 m <sup>3</sup>
③	埋 戻	18.7 m <sup>3</sup>
④	盛 土	0.0 m <sup>3</sup>

残 土 処 理	18.6 m <sup>3</sup>
( 機械掘削 + 機械床掘 - 埋戻/0.9 - 盛土/0.9 )	

測点	単距離	断 面				平均断面				立 積				適 要
		①	②	③	④	①	②	③	④	①	②	③	④	
B.P	0.00		1.0	0.4										
No.1	20.00		0.8	0.4		0.90	0.40			18.0	8.0			
No.2	20.00		0.8	0.4		0.80	0.40			16.0	8.0			
+3.9	3.90		0.8	0.4		0.80	0.40			3.1	1.6			
+6.0	2.10		1.4	0.6		1.10	0.50			2.3	1.1			
	46.00									0.0	39.4	18.7	0.0	

# 計 算 表

## 浜田町4号線

⑤ 不陸整正	98.7 m <sup>2</sup>
⑥	0.0 m <sup>3</sup>
⑦	0.0 m <sup>3</sup>
⑧	0.0 m <sup>3</sup>

測点	単距離	断 面				平均断面				立 積				適 要
		⑤	⑥	⑦	⑧	⑤	⑥	⑦	⑧	⑤	⑥	⑦	⑧	
B.P	0.00	2.0												
No.1	20.00	2.0				2.00				40.0				
No.2	20.00	2.0				2.00				40.0				
+3.9	3.90	2.0				2.00				7.8				
+6.0	2.10	8.4				5.20				10.9				
合計	46.00									98.7	0.0	0.0	0.0	