

数量計算書

 $1/2$ [illegible]

数量計算書

2/2

[illegible]

【土木関係数量拾い出し表】

φ500x1900		数量	1基当たり							
防蝕塗装 φ168 ▽ G.L. 電線管 接地棒 コンクリート クラッシャーラン φ500 φ600 1900 1800 50 50 100										
					基礎 砕石	RC-40 0.6×0.6×1/4×3.14×0.1	0.028 m ³	掘削	0.6×0.6×1/4×3.14×2.3	0.650 m ³
					円形 型枠	φ500 スパイラルダクト	1.900 m	埋め戻し	0.6×0.6×1/4×3.14×0.3	0.085 m ³
					コン クリート	18N/mm ² 0.5×0.5×1/4×3.14×1.9	0.373 m ³	残土 処理	0.65-0.085	0.565 m ³
					アン カー ボルト	4-M24×700 高ナット	1.000 組	間詰 砂	0.65-0.373-0.028-0.085	0.164 m ³
					連結 式接 地棒	φ10-1,500 φ10リード端子	1.000 組			
					硬質 ビニ ル電 線管	VE16	1.000 m			
					電 線	IV 3.5sq	2.000 m			